

C.200

TYPICAL SIGNAGE NOTES	
1.	BUILDINGS SHALL HAVE APPROVED ADDRESS NUMBERS, BUILDING NUMBERS OR APPROVED BUILDING IDENTIFICATION PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY.
2.	BUILDING NUMBERS SHALL CONTRAST WITH THEIR BACKGROUND.
3.	ADDRESS NUMBERS SHALL BE ARABIC NUMERALS OR ALPHABETICAL LETTERS.
4.	NUMBERS SHALL BE A MINIMUM OF 4" HIGH WITH A MINIMUM STROKE WIDTH OF 1/2".

TYPICAL STUCCO NOTES	
1.	WEEP SCREED SHALL BE APPLIED AT ENTIRE PERIMETER OF FOUNDATION. PLACE LINE AT A MINIMUM 6" ABOVE FINISHED GRADE.
2.	METAL LATH SHALL BE INSTALLED OVER 60 MIN. GRADE 'D' BUILDING PAPER PER ASTM C-1063 REQUIREMENTS.
3.	REFER TO DETAIL 14/A7.31 FOR STUCCO ACCESSORY DETAILS.
4.	CONTROL JOINTS SHALL BE INSTALLED PER ASTM C-1063 REQUIREMENTS INCLUDING: 4.1. CONTROL JOINTS TO BE INSTALLED IN WALLS TO DELINEATE AREAS NOT LARGER THAN 144 SQ.FT. 4.2. DISTANCE BETWEEN CONTROL JOINTS SHALL NOT EXCEED 18'-0" IN EITHER DIRECTION OR A LENGTH TO WIDTH RATIO OF 2.5 : 1. 4.3. EXPANSION JOINTS SHALL BE INSTALLED AT ALL FLOOR LINES. 4.4. METAL LATH SHALL BE DIS-CONTINUOUS (CUT) AT CONTROL JOINTS. DO NOT CUT BUILDING PAPER LATH IS NOT REQUIRED TO BE CUT AT AESTHETIC JOINTS. WHERE JOINTS SHOWN ON ELEVATIONS EXCEED THE REQUIREMENTS OF ASTM C-1063, CONTRACTOR MAY EXERCISE OPTION TO CUT ONLY JOINTS SO AS TO COMPLY WITH ASTM C-1063.

ELEVATION GENERAL NOTES			
1.	TYPICAL EXTERIOR CLADDING: COMBINATION OF FIBER CEMENT PANELS, FIBER CEMENT SIDING, AND STONE VENEER INSTALLED OVER STUCCO. CORNERS OF BUILDINGS TO RECEIVE 12" WIDE SELF-ADHERING MEMBRANE FLASHING. ALL OPENINGS SHALL BE INSTALLED PER DETAILS PROVIDED ON SHEETS A7.11 - A7.21.	2.	PROVIDE CONTROL JOINTS WHERE WOOD-FRAME AND CMU WALLS MEET.
3.	ENTIRE BUILDING SHALL RECEIVE BUILDING WRAP. INSIDE AND OUTSIDE CORNERS SHALL BE PRE-WRAPPED WITH SELF-ADHERING MEMBRANE FOR 6" ON EACH SIDE OF CORNER.	4.	ALL FINISH GRADES SHALL BE A MINIMUM 8" BELOW FINISH FLOOR AND SLOPE AWAY FROM BUILDING.
5.	PROVIDE UV-RATED URETHANE SEALANT AT ALL INSIDE CORNERS AND WINDOW/DOOR PERIMETERS.	6.	TO PREVENT MOISTURE INTRUSION, ALL PENETRATIONS MUST BE PROPERLY FLASHED AND/OR SEALED. ATTACHMENTS THROUGH EXTERIOR SKIN SHALL BE SET IN FULL BED OF SEALANT. REFER TO SHEET A7.42 FOR DETAILS.
7.	ALL BUILDING-MOUNTED EQUIPMENT SHALL BE MOUNTED AFTER EXTERIOR FINISH IS APPLIED AND PAINTED. IF SEQUENCING OF CONSTRUCTION REQUIRES MOUNTING PRIOR TO THIS, CONTRACTOR SHALL SUBMIT METHOD OF MOUNTING AND WATERPROOFING TO ARCHITECT FOR APPROVAL.	8.	ALL UNIT BALCONIES TO HAVE STRUCTURAL FLOOR SYSTEMS SLOPED MIN. 1/4"; 1'-0" AWAY FROM BUILDING FOR DRAINAGE.
9.	PROVIDE URETHANE SEALANT WITH BOND BREAKER (TO PREVENT 3-SIDED ADHESION) AT TOP AND BOTTOM OF HORIZONTAL BUILDING BANDS.	10.	PROVIDE 1:2 SLOPE AT TOP OF HORIZONTAL TRIM.
11.	PROVIDE SEALANT JOINTS AT INTERFACES BETWEEN DISSIMILAR MATERIALS, SUCH AS BALCONY CEILINGS, BALCONY EXTERIOR EDGES, ETC.	12.	INDICATES SUGGESTED GUTTER AND DOWNSPOUT LOCATION - PROVIDE SPLASH BLOCK AT EACH DOWNSPOUT. REFER TO SHEET A7.51 FOR DETAILS.
13.	EXTERIOR WALLS TO BE PAINTED PRIOR TO INSTALLATION OF DOWNSPOUTS.	14.	PROVIDE SUFFICIENT BLOCKING FOR ALL DECORATIVE ATTACHMENTS AND CONFIRM VIA SHOP DRAWINGS.

ELEVATION KEY NOTES	
1	30-YEAR ARCHITECTURAL STYLE SHINGLES OVER ROOF UNDERLAYMENT PER SPECS AND ENERGY CALCULATIONS
2	FIBER CEMENT FASCIA PANEL
3	FIBER CEMENT PANEL AND TRIM SYSTEM OVER BUILDING WRAP OVER EXTERIOR SHEATHING INSTALLED PER U.L. U356
4	FIBER CEMENT LAP SIDING SYSTEM WITH 6" OVERLAP
5	FIBER CEMENT LAP SIDING SYSTEM WITH 10" OVERLAP
6	42" HIGH ALUMINUM RAILING
7	DECORATIVE BRACKET
8	EXT. WINDOW - REFER TO PLANS AND SCHEDULE FOR DETAILS
9	STOREFRONT SYSTEM - MUST MEET MIN. REQUIREMENTS FOR WIND LOADS AND ENERGY CALCULATIONS
10	STONE VENEER OVER 2-COAT STUCCO SYSTEM OVER BLDG WRAP OVER EXTERIOR SHEATHING INSTALLED PER U.L. U356
11	ALUMINUM SCREEN ENCLOSURE SYSTEM WITH INTEGRATED 42" GUARDRAIL
12	STANDING SEAM METAL ROOF SYSTEM
13	DECORATIVE SHUTTERS
14	OVERHEAD GARAGE DOOR - REFER TO SHEETS A7.01 AND A7.11 FOR ADD'L INFO.
15	ELECTRICAL METERS
16	VENT - REFER TO MEP DRAWINGS
17	LIGHT FIXTURE - REFER TO ELECTRICAL SCHEDULE FOR DETAILS



4 CLUBHOUSE - LEFT ELEVATION



3 CLUBHOUSE - REAR ELEVATION



2 CLUBHOUSE - RIGHT ELEVATION



1 CLUBHOUSE - FRONT ELEVATION

INTEGRA TWENTY FOUR
GAINESVILLE, FLORIDA

c b a
charlan • brock
associates
architects planners


1770 fennell street
maitland florida 32751-7208
407 660 8900 f: 407 875 9948
www.cbaarchitects.com

CLUBHOUSE
EXTERIOR ELEVATIONS

date: 07-10-2017
job no: 3914.16
drawn by: CRL
reviewed by: CBA
file: 3914A2.51
issue history:

A2.51
181

DESIGN DEVELOPMENT - NOT FOR CONSTRUCTION



charlan, brock & associates, inc. hereby reserves its common law copyright and other property rights in these plans, ideas, and designs. These ideas, designs, and plans are not to be reproduced, changed or copied in any form or manner whatsoever, nor are they to be assigned to any third party, without first obtaining the express written permission from c.b.a., inc. written dimensions shall have precedence over scale dimensions.

TYPICAL SIGNAGE NOTES	
1.	BUILDINGS SHALL HAVE APPROVED ADDRESS NUMBERS, BUILDING NUMBERS OR APPROVED BUILDING IDENTIFICATION PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY.
2.	BUILDING NUMBERS SHALL CONTRAST WITH THEIR BACKGROUND.
3.	ADDRESS NUMBERS SHALL BE ARABIC NUMERALS OR ALPHABETICAL LETTERS.
4.	NUMBERS SHALL BE A MINIMUM OF 4" HIGH WITH A MINIMUM STROKE WIDTH OF 1/2".

TYPICAL STUCCO NOTES	
1.	WEEP SCREED SHALL BE APPLIED AT ENTIRE PERIMETER OF FOUNDATION. PLACE LINE AT A MINIMUM 6" ABOVE FINISHED GRADE.
2.	METAL LATH SHALL BE INSTALLED OVER 60 MIN. GRADE 'D' BUILDING PAPER PER ASTM C-1063 REQUIREMENTS.
3.	REFER TO DETAIL 14/A7.31 FOR STUCCO ACCESSORY DETAILS.
4.	CONTROL JOINTS SHALL BE INSTALLED PER ASTM C-1063 REQUIREMENTS INCLUDING: 4.1. CONTROL JOINTS TO BE INSTALLED IN WALLS TO DELINEATE AREAS NOT LARGER THAN 144 SQ.FT. 4.2. DISTANCE BETWEEN CONTROL JOINTS SHALL NOT EXCEED 18'-0" IN EITHER DIRECTION OR A LENGTH TO WIDTH RATIO OF 2.5 : 1. 4.3. EXPANSION JOINTS SHALL BE INSTALLED AT ALL FLOOR LINES. 4.4. METAL LATH SHALL BE DIS-CONTINUOUS (CUT) AT CONTROL JOINTS. DO NOT CUT BUILDING PAPER. LATH IS NOT REQUIRED TO BE CUT AT AESTHETIC JOINTS, WHERE JOINTS SHOWN ON ELEVATIONS EXCEED THE REQUIREMENTS OF ASTM C-1063. CONTRACTOR MAY EXERCISE OPTION TO CUT ONLY JOINTS SO AS TO COMPLY WITH ASTM C-1063.

ELEVATION GENERAL NOTES	
1.	TYPICAL EXTERIOR CLADDING: COMBINATION OF FIBER CEMENT PANELS, FIBER CEMENT SIDING, AND STONE VENEER INSTALLED OVER STUCCO. CORNERS OF BUILDINGS TO RECEIVE 12" WIDE SELF-ADHERING MEMBRANE FLASHING. ALL OPENINGS SHALL BE INSTALLED PER DETAILS PROVIDED ON SHEETS A7.11 - A7.21.
2.	PROVIDE CONTROL JOINTS WHERE WOOD-FRAME AND CMU WALLS MEET.
3.	ENTIRE BUILDING SHALL RECEIVE BUILDING WRAP. INSIDE AND OUTSIDE CORNERS SHALL BE PRE-WRAPPED WITH SELF-ADHERING MEMBRANE FOR 6" ON EACH SIDE OF CORNER.
4.	ALL FINISH GRADES SHALL BE A MINIMUM 8" BELOW FINISH FLOOR AND SLOPE AWAY FROM BUILDING.
5.	PROVIDE UV-RATED URETHANE SEALANT AT ALL INSIDE CORNERS AND WINDOW/DOOR PERIMETERS.
6.	TO PREVENT MOISTURE INTRUSION, ALL PENETRATIONS MUST BE PROPERLY FLASHED AND/CORE SEALED. ATTACHMENTS THROUGH EXTERIOR SKIN SHALL BE SET IN FULL BED OF SEALANT. REFER TO SHEET A7.42 FOR DETAILS.
7.	ALL BUILDING-MOUNTED EQUIPMENT SHALL BE MOUNTED AFTER EXTERIOR FINISH IS APPLIED AND PAINTED. IF SEQUENCING OF CONSTRUCTION REQUIRES MOUNTING PRIOR TO THIS, CONTRACTOR SHALL SUBMIT METHOD OF MOUNTING AND WATERPROOFING TO ARCHITECT FOR APPROVAL.
8.	ALL UNIT BALCONIES TO HAVE STRUCTURAL FLOOR SYSTEMS SLOPED MIN. 1/4" : 1'-0" AWAY FROM BUILDING FOR DRAINAGE.
9.	PROVIDE URETHANE SEALANT WITH BOND BREAKER (TO PREVENT 3-SIDED ADHESION) AT TOP AND BOTTOM OF HORIZONTAL BUILDING BANDS.
10.	PROVIDE 1:2 SLOPE AT TOP OF HORIZONTAL TRIM.
11.	PROVIDE SEALANT JOINTS AT INTERFACES BETWEEN DISSIMILAR MATERIALS, SUCH AS BALCONY CEILINGS, BALCONY EXTERIOR EDGES, ETC.
12.	INDICATES SUGGESTED GUTTER AND DOWNSPOUT LOCATION - PROVIDE SPLASH BLOCK AT EACH DOWNSPOUT. REFER TO SHEET A7.51 FOR DETAILS.
13.	EXTERIOR WALLS TO BE PAINTED PRIOR TO INSTALLATION OF DOWNSPOUTS.
14.	PROVIDE SUFFICIENT BLOCKING FOR ALL DECORATIVE ATTACHMENTS AND CONFIRM VIA SHOP DRAWINGS.

ELEVATION KEY NOTES	
1	30-YEAR ARCHITECTURAL STYLE SHINGLES OVER ROOF UNDERLAYMENT PER SPECS OVER ROOF SHEATHING ON PRE-FABRICATED WOOD TRUSSES
2	FIBER CEMENT FASCIA PANEL
3	FIBER CEMENT PANEL AND TRIM SYSTEM OVER BUILDING WRAP OVER EXTERIOR SHEATHING INSTALLED PER U.L. U356
4	FIBER CEMENT LAP SIDING SYSTEM WITH 6" OVERLAP
5	FIBER CEMENT LAP SIDING SYSTEM WITH 10" OVERLAP
6	42" HIGH ALUMINUM RAILING
7	DECORATIVE BRACKET
8	EXT. WINDOW - REFER TO PLANS AND SCHEDULE FOR DETAILS
9	STOREFRONT SYSTEM - MUST MEET MIN. REQUIREMENTS FOR WIND LOADS AND ENERGY CALCULATIONS
10	STONE VENEER OVER 2-COAT STUCCO SYSTEM OVER BLDG WRAP OVER EXTERIOR SHEATHING INSTALLED PER U.L. U356
11	ALUMINUM SCREEN ENCLOSURE SYSTEM WITH INTEGRATED 42" GUARDRAIL
12	STANDING SEAM METAL ROOF SYSTEM
13	DECORATIVE SHUTTERS
14	OVERHEAD GARAGE DOOR - REFER TO SHEETS A7.01 AND A7.11 FOR ADD'L INFO.
15	ELECTRICAL METERS
16	VENT - REFER TO MEP DRAWINGS
17	LIGHT FIXTURE - REFER TO ELECTRICAL SCHEDULE FOR DETAILS



1 BUILDING TYPE ONE - FRONT ELEVATION

SCALE: 1/16"=1'-0"

DESIGN DEVELOPMENT - NOT FOR CONSTRUCTION

date: 07-10-2017
job no: 3914.16
drawn by: CL
reviewed by: CBA
file: 3914A2.11
issue history:

BUILDING TYPE ONE
EXTERIOR ELEVATIONS


1770 fennell street
maifland florida 32751-7208
407 660 8900 f: 407 875 9948
www . cbaarchitects . com

architects planners

c b a
charlan • brock
associates

INTEGRA LAND COMPANY, LLC
1525 INTERNATIONAL PARKWAY, SUITE 2001
LAKE MARY, FL 32746
PH. 407-833-3927

INTEGRA TWENTY FOUR
GAINESVILLE, FLORIDA



FHA # 063-35358

A2.11




1 BUILDING TYPE TWO - FRONT ELEVATION

SCALE: 1/16"=1'-0"

TYPICAL SIGNAGE NOTES 1. BUILDINGS SHALL HAVE APPROVED ADDRESS NUMBERS, BUILDING NUMBERS OR APPROVED BUILDING IDENTIFICATION PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY. 2. BUILDING NUMBERS SHALL CONTRAST WITH THEIR BACKGROUND. 3. ADDRESS NUMBERS SHALL BE ARABIC NUMERALS OR ALPHABETICAL LETTERS. 4. NUMBERS SHALL BE A MINIMUM OF 4" HIGH WITH A MINIMUM STROKE WIDTH OF 1/2".	TYPICAL STUCCO NOTES 1. WEEP SCREED SHALL BE APPLIED AT ENTIRE PERIMETER OF FOUNDATION. PLACE LINE AT A MINIMUM 6" ABOVE FINISHED GRADE. 2. METAL LATH SHALL BE INSTALLED OVER 60 MIN. GRADE 'D' BUILDING PAPER PER ASTM C-1063 REQUIREMENTS. 3. REFER TO DETAIL 14/A7.31 FOR STUCCO ACCESSORY DETAILS. 4. CONTROL JOINTS SHALL BE INSTALLED PER ASTM C-1063 REQUIREMENTS INCLUDING: 4.1. CONTROL JOINTS TO BE INSTALLED IN WALLS TO DELINEATE AREAS NOT LARGER THAN 144 SQ.FT. 4.2. DISTANCE BETWEEN CONTROL JOINTS SHALL NOT EXCEED 18'-0" IN EITHER DIRECTION OR A LENGTH TO WIDTH RATIO OF 2.5 : 1. 4.3. EXPANSION JOINTS SHALL BE INSTALLED AT ALL FLOOR LINES. 4.4. METAL LATH SHALL BE DIS-CONTINUOUS (CUT) AT CONTROL JOINTS. DO NOT CUT BUILDING PAPER. LATH IS NOT REQUIRED TO BE CUT AT AESTHETIC JOINTS. WHERE JOINTS SHOWN ON ELEVATIONS EXCEED THE REQUIREMENTS OF ASTM C-1063, CONTRACTOR MAY EXERCISE OPTION TO CUT ONLY JOINTS SO AS TO COMPLY WITH ASTM C-1063.	ELEVATION GENERAL NOTES 1. TYPICAL EXTERIOR CLADDING: COMBINATION OF FIBER CEMENT PANELS, FIBER CEMENT SIDING, AND STONE VENEER INSTALLED OVER STUCCO. CORNERS OF BUILDINGS TO RECEIVE 12" WIDE SELF-ADHERING MEMBRANE FLASHING. ALL OPENINGS SHALL BE INSTALLED PER DETAILS PROVIDED ON SHEETS A7.11 - A7.21. 2. PROVIDE CONTROL JOINTS WHERE WOOD-FRAME AND CMU WALLS MEET. 3. ENTIRE BUILDING SHALL RECEIVE BUILDING WRAP. INSIDE AND OUTSIDE CORNERS SHALL BE PRE-WRAPPED WITH SELF-ADHERING MEMBRANE FOR 6" ON EACH SIDE OF CORNER. 4. ALL FINISH GRADES SHALL BE A MINIMUM 8" BELOW FINISH FLOOR AND SLOPE AWAY FROM BUILDING. 5. PROVIDE UV-RATED URETHANE SEALANT AT ALL INSIDE CORNERS AND WINDOW/DOOR PERIMETERS. 6. TO PREVENT MOISTURE INTRUSION, ALL PENETRATIONS MUST BE PROPERLY FLASHED AND/OR SEALED. ATTACHMENTS THROUGH EXTERIOR SKIN SHALL BE SET IN FULL BED OF SEALANT. REFER TO SHEET A7.42 FOR DETAILS. 7. ALL BUILDING-MOUNTED EQUIPMENT SHALL BE MOUNTED AFTER EXTERIOR FINISH IS APPLIED AND PAINTED. IF SEQUENCING OF CONSTRUCTION REQUIRES MOUNTING PRIOR TO THIS, CONTRACTOR SHALL SUBMIT METHOD OF MOUNTING AND WATERPROOFING TO ARCHITECT FOR APPROVAL. 8. ALL UNIT BALCONIES TO HAVE STRUCTURAL FLOOR SYSTEMS SLOPED MIN. 1/4" : 1'-0" AWAY FROM BUILDING FOR DRAINAGE. 9. PROVIDE URETHANE SEALANT WITH BOND BREAKER (TO PREVENT 3-SIDED ADHESION) AT TOP AND BOTTOM OF HORIZONTAL BUILDING BANDS. 10. PROVIDE 1:2 SLOPE AT TOP OF HORIZONTAL TRIM. 11. PROVIDE SEALANT JOINTS AT INTERFACES BETWEEN DISSIMILAR MATERIALS, SUCH AS BALCONY CEILINGS, BALCONY EXTERIOR EDGES, ETC. 12. INDICATES SUGGESTED GUTTER AND DOWNSPOUT LOCATION - PROVIDE SPLASH BLOCK AT EACH DOWNSPOUT. REFER TO SHEET A7.51 FOR DETAILS. 13. EXTERIOR WALLS TO BE PAINTED PRIOR TO INSTALLATION OF DOWNSPOUTS. 14. PROVIDE SUFFICIENT BLOCKING FOR ALL DECORATIVE ATTACHMENTS AND CONFIRM VIA SHOP DRAWINGS.	ELEVATION KEY NOTES 1 30-YEAR ARCHITECTURAL STYLE SHINGLES OVER ROOF UNDERLAYMENT PER SPECS OVER ROOF SHEATHING ON PRE-FABRICATED WOOD TRUSSES 2 FIBER CEMENT FASCIA PANEL 3 FIBER CEMENT PANEL AND TRIM SYSTEM OVER BUILDING WRAP OVER EXTERIOR SHEATHING INSTALLED PER U.L. U356 4 FIBER CEMENT LAP SIDING SYSTEM WITH 6" OVERLAP 5 FIBER CEMENT LAP SIDING SYSTEM WITH 10" OVERLAP 6 42" HIGH ALUMINUM RAILING 7 DECORATIVE BRACKET 8 EXT. WINDOW - REFER TO PLANS AND SCHEDULE FOR DETAILS 9 STOREFRONT SYSTEM - MUST MEET MIN. REQUIREMENTS FOR WIND LOADS AND ENERGY CALCULATIONS 10 STONE VENEER OVER 2-COAT STUCCO SYSTEM OVER BLDG WRAP OVER EXTERIOR SHEATHING INSTALLED PER U.L. U356 11 ALUMINUM SCREEN ENCLOSURE SYSTEM WITH INTEGRATED 42" GUARDRAIL 12 STANDING SEAM METAL ROOF SYSTEM 13 DECORATIVE SHUTTERS 14 OVERHEAD GARAGE DOOR - REFER TO SHEETS A7.01 AND A7.11 FOR ADD'L INFO. 15 ELECTRICAL METERS 16 VENT - REFER TO MEP DRAWINGS 17 LIGHT FIXTURE - REFER TO ELECTRICAL SCHEDULE FOR DETAILS
--	---	--	--

DESIGN DEVELOPMENT - NOT FOR CONSTRUCTION

INTEGRA TWENTY FOUR
GAINESVILLE, FLORIDA




1770 fennell street
maitland florida 32751-7208
407 660 8900 f: 407 875 9948
www . cbaarchitects . com

BUILDING TYPE TWO
EXTERIOR ELEVATIONS

date: 07-10-2017
job no: 3914.16
drawn by: CL
reviewed by: CBA
file: 3914A2.21
issue history:


A2.21



INTEGRA LAND COMPANY, LLC
1525 INTERNATIONAL PARKWAY, SUITE 2001
LAKE MARY, FL 32746
PH: 407-833-3927
FHA # 063-35358

V:\2156\active\215613831\Drawings_CAD\Landscape_2\res_Plan.dwg
2017/07/10 11:29 AM By: Buck, Etc

ORIGINAL SHEET - ARCH D 24036




LANDSCAPE LEGEND

LANDSCAPE NOTES


1. SEE PLANT LIST FOR SIZE AND SPECIFICATIONS, TYPICAL.
2. PLANT MATERIAL SHALL CONFORM TO STANDARDS FOR FLORIDA #1 OR BETTER AS STATED IN THE LATEST EDITION OF FLORIDA GRADES AND STANDARDS FOR NURSERY PLANTS, PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUME SERVICES, TYPICAL.
3. CONTAINER SIZE SHOWN IS A MINIMUM BASED ON TYPICAL INDUSTRY AVAILABILITY. IF CODE REQUIREMENTS CANNOT BE MET WITH CONTAINER SIZE SHOWN, UP SIZE MATERIAL AS REQUIRED TO MEET ALL APPLICABLE CODES, TYPICAL.
4. SEE HARDSCAPE NOTES.

LANDSCAPE ANNOTATION


PLANT TAG




TREE SYMBOL




SOD / LAWN



MULCH AREA



ANNUALS



Stantec Consulting Services Inc.
479 New Broad Street, Suite 100
Orlando, FL
Tel. 407-425-2500
www.stantec.com

Copyright Reserved


The Contractor shall verify and be responsible for all dimensions, DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Consultants

Legend

Notes

KEY PLAN



Revision

Revision	By	Appd.	YY.MM.DD
GRU SUBMITAL			07.10.2017
Issued	By	Appd.	YY.MM.DD

File Name: _____
Dwn. Chkd. Dgn. YY.MM.DD

Permit-Seal

Client/Project

INTEGRA TWENTY FOUR

GAINESVILLE, FL.

Title

LANDSCAPE PLAN
TREE PLANTING

Project No.

215613831

Scale

as shown

Drawing No.

LT.01


Sheet

of

Revision

0

V:\2156\active\215613831\Drawings_CAD\Landscape_2\res_Plan.dwg
2017/07/10 11:30 AM By: Buck, Etc



LANDSCAPE LEGEND

LANDSCAPE NOTES

1. SEE PLANT LIST FOR SIZE AND SPECIFICATIONS, TYPICAL.
2. PLANT MATERIAL SHALL CONFORM TO STANDARDS FOR FLORIDA #1 OR BETTER AS STATED IN THE LATEST EDITION OF FLORIDA GRADES AND STANDARDS FOR NURSERY PLANTS, PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUME SERVICES, TYPICAL.
3. CONTAINER SIZE SHOWN IS A MINIMUM BASED ON TYPICAL INDUSTRY AVAILABILITY. IF CODE REQUIREMENTS CANNOT BE MET WITH CONTAINER SIZE SHOWN, UP SIZE MATERIAL AS REQUIRED TO MEET ALL APPLICABLE CODES, TYPICAL.
4. SEE HARDSCAPE NOTES.

LANDSCAPE ANNOTATION

PLANT TAG


QUE VIR-3
4

PLANT SYMBOL
PLANT QUANTITY


TREE SYMBOL

PROPOSED TREE
EXPECTED 20 YEAR GROWTH


SOD / LAWN



MULCH AREA



ANNUALS




APPROXIMATE LOCATION OF EXISTING TREES ON CITY PROPERTY. CITY TO FIELD IDENTIFY TREES THAT MAY NEED TREE REMOVAL FOR SAFE SIGHT DISTANCE TRIANGLE AND ACCESS CONSTRUCTION

MANHOLE G
N. RIM 71.00'
8" PVC N. INV
8" PVC S. INV
8" PVC E INV
4" PVC W INV

APPROXIMATE LOCATION OF EXISTING TREES ON CITY PROPERTY. CITY TO FIELD IDENTIFY TREES THAT MAY NEED TREE REMOVAL FOR SAFE SIGHT DISTANCE TRIANGLE AND ACCESS CONSTRUCTION

EXISTING STREET TREES ON CITY PROPERTY



NORTH
SCALE 1"=20'-0"



Stantec Consulting Services Inc.
479 New Broad Street, Suite 100
Orlando, FL
Tel. 407-425-2500
www.stantec.com

Copyright Reserved


The Contractor shall verify and be responsible for all dimensions, DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Consultants

Legend

Notes

KEY PLAN



Revision	By	Appd.	YY.MM.DD
GRU SUBMITAL			07.10.2017
Issued	By	Appd.	YY.MM.DD

File Name: _____
Dwn. Chkd. Dsgn. YY.MM.DD
Permit-Seal


Client/Project
INTEGRA TWENTY FOUR

GAINESVILLE, FL.

Title
LANDSCAPE PLAN
TREE PLANTING

Project No. 215613831 Scale as shown
Drawing No. LT.02 Sheet of 0

V:\2156\active\215613831\Drawings_CAD\Landscape_2\Tree_Plan.dwg
2017/07/10 11:31 AM By: Buck, Etc



LANDSCAPE LEGEND

LANDSCAPE NOTES

- SEE PLANT LIST FOR SIZE AND SPECIFICATIONS, TYPICAL.
- PLANT MATERIAL SHALL CONFORM TO STANDARDS FOR FLORIDA #1 OR BETTER AS STATED IN THE LATEST EDITION OF FLORIDA GRADES AND STANDARDS FOR NURSERY PLANTS, PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUME SERVICES, TYPICAL.
- CONTAINER SIZE SHOWN IS A MINIMUM BASED ON TYPICAL INDUSTRY AVAILABILITY. IF CODE REQUIREMENTS CANNOT BE MET WITH CONTAINER SIZE SHOWN, UP SIZE MATERIAL AS REQUIRED TO MEET ALL APPLICABLE CODES, TYPICAL.
- SEE HARDSCAPE NOTES.

LANDSCAPE ANNOTATION

PLANT TAG

QUE VIR-3

4

PLANT SYMBOL


PLANT QUANTITY

TREE SYMBOL


PROPOSED TREE

EXPECTED 20 YEAR GROWTH


SOD / LAWN



MULCH AREA



ANNUALS



Stantec Consulting Services Inc.
479 New Broad Street, Suite 100
Orlando, FL
Tel. 407-425-2500
www.stantec.com

Copyright Reserved


The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Consultants

Legend

Notes

KEY PLAN



Revision

Revision	By	Appd.	YY.MM.DD
GRU SUBMITAL			07.10.2017
Issued	By	Appd.	YY.MM.DD

File Name:

File Name: _____ Dwn. Chkd. Dgrr. YY.MM.DD

Permit-Seal

Client/Project

INTEGRA TWENTY FOUR

GAINESVILLE, FL.

Title

LANDSCAPE PLAN
TREE PLANTING

Project No.

215613831

Drawing No.

LT.03

Scale
as shown


Sheet

of

Revision

0

V:\2156\active\215613831\Drawings_CAD\Landscape_Tree_Plan.dwg
2017/07/10 11:31 AM By: Buck, Etc



LANDSCAPE LEGEND

LANDSCAPE NOTES

- SEE PLANT LIST FOR SIZE AND SPECIFICATIONS, TYPICAL.
- PLANT MATERIAL SHALL CONFORM TO STANDARDS FOR FLORIDA #1 OR BETTER AS STATED IN THE LATEST EDITION OF FLORIDA GRADES AND STANDARDS FOR NURSERY PLANTS, PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUME SERVICES, TYPICAL.
- CONTAINER SIZE SHOWN IS A MINIMUM BASED ON TYPICAL INDUSTRY AVAILABILITY. IF CODE REQUIREMENTS CANNOT BE MET WITH CONTAINER SIZE SHOWN, UP SIZE MATERIAL AS REQUIRED TO MEET ALL APPLICABLE CODES, TYPICAL.
- SEE HARDSCAPE NOTES.

LANDSCAPE ANNOTATION

PLANT TAG

QUE VIR-3
4
PLANT SYMBOL
PLANT QUANTITY


TREE SYMBOL

PROPOSED TREE
EXPECTED 20 YEAR GROWTH


SOD / LAWN



MULCH AREA



ANNUALS



Stantec Consulting Services Inc.
479 New Broad Street, Suite 100
Orlando, FL
Tel. 407-425-2500
www.stantec.com

Copyright Reserved


The Contractor shall verify and be responsible for all dimensions, DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Consultants

Legend

Notes

KEY PLAN



Revision

Revision	By	Appd.	YY.MM.DD
GRU SUBMITTAL			07.10.2017
Issued	By	Appd.	YY.MM.DD

File Name: _____
Dwn. Chkd. Dgn. YY.MM.DD

Permit-Seal

Client/Project
INTEGRA TWENTY FOUR

GAINESVILLE, FL.

Title
LANDSCAPE PLAN
TREE PLANTING


Project No. 215613831 Scale as shown
Drawing No. Sheet Revision

LT.04

of

0

McGre Engineers, LLC - 17035-MEP-SITE.dwg - U0.10 - Plotted: Tuesday, December 05, 2017 by Henry Stewart



- 1 COORDINATE FIRE RISER AND COLD WATER LOCATION WITH CIVIL, AND WITH INDIVIDUAL BUILDING PLANS.
- 2 COORDINATE SANITARY PIPING LOCATION WITH CIVIL, AND WITH INDIVIDUAL BUILDING PLANS.

INTEGRA TWENTY FOUR
GAINESVILLE, FLORIDA

charlan • brock
associates


architects • planners
1770 fennell street
maitland florida 32751-7208
407 660 8900 f: 407 875 9948
www.cbaarchitects.com

MEP CONNECTIONS


SITE PLAN

date: 06-16-2017
job no: 3914.16
drawn by: GHK/MLD
reviewed by: GHK/MLD
file: 17035-MEP-SITE
issue history:

U0.10



1200 W. SR 434
SUITE 301
LONGWOOD, FL 32750
PH: 407.536.7999
PROJECT #: 17035



INTEGRA LAND COMPANY, LLC
1525 INTERNATIONAL PARKWAY, SUITE 2001
LAKE MARY, FL 32746
PH: 407-833-3927

charlan • brock
associates


architects • planners
1770 fennell street
maitland florida 32751-7208
407 660 8900 f: 407 875 9948
www.cbaarchitects.com

MEP CONNECTIONS

SITE PLAN

date: 06-16-2017
job no: 3914.16
drawn by: GHK/MLD
reviewed by: GHK/MLD
file: 17035-MEP-SITE
issue history:

U0.10



INTEGRA TWENTY FOUR
GAINESVILLE, FLORIDA

charlan • brock
associates
architects • planners

1770 fennell street
maitland florida 32751-7208
407 660 8900 f: 407 875 5948
www.cbaarchitects.com

PHOTOMETRIC
SITE PLAN

date: 06-16-2017
job no: 3914.16
drawn by: MLD
reviewed by: MLD
file: 17035-E-SITE
issue history:

EO.11

Micro Engineers, LLC
1200 W. SR 434
SUITE 301
LONGWOOD, FL 32750
PH: 407.536.7999
PROJECT #: 17035

Professional Engineer
No. 44665
STATE OF FLORIDA

INTEGRA LAND COMPANY, LLC
1525 INTERNATIONAL PARKWAY, SUITE 201
LAKE MARY, FL 32746
PH: 407-833-3927

Florida
AAC000798