




Legislative ID# 160287F


































# Changes in land use affect nitrogen loading The proposed Alachua County stormwater manual will only have an impact on new development or redevelopment of existing sites Does not reduce nitrogen loading from existing developments Does not reduce nitrogen loading from existing developments Agricultus Mattewerer Agricultus Mattew



# Alachua County Stormwater Quality Treatment Manual Relation to Municipal Requirements The current draft manual is intended for use in unincorporated portions of Alachua County A new manual for municipalities will be created Flood control (water quantity) will be based each municipality's code Water quality requirements will be established by the County manual



# How?



### **Alachua County Stormwater Quality Treatment Manual**

🐁 Fundamental Basis of the Manual - Groundwater Quality

### New Performance Standards (Continued):

- 4. Projects within SKA (e.g. Newberry) must reduce nitrate loading into groundwater by 70%
- Applicable to stormwater that <u>infiltrates</u> within a retention basin
- Pollutant load reduction is quantified by the amount of nutrient that is retained and does not percolate into the aquifer
- Retention basins in SKA require a min. depth of 2 feet of Bio-Sorption Activated Media (BAM) over the bottom and side banks of the basin

плотить финура выску пожерыторого колитиского

DOMESTING FOR CORRECT

# How?



### **Alachua County Stormwater Quality Treatment Manual**

### **Best Management Practices (BMPs)**

- BMPs are tools used to reduce pollutant loading to ground and surface waters
- Two types of BMPs: Structural and Non-Structural

### **Structural**

- Wet ponds, dry ponds, swales, rain gardens, etc.
- Design requirements and principles for system components
- Following the guidelines results in an presumed reduction in pollutant load


### Non-structural (Site planning & Source Control)

- Low impact design (LID) reduce impervious area, DCIA, treatment train approach
- Florida Friendly Landscaping and fertilizer applications
- Following these practices yields load reduction credits to meet the performance standards

allandia) da ago surkumu majooman construction

20100(##\$\$4500H C@H#00####

# What is BAM? Bio-Sorption Activated Media BAM is a BMP that helps with the removal of the primary pollutants as identified by Alachua County: Total Phosphorus (TP), Total Nitrogen (TN), and Total Suspended Solids (TSS) from storm water. TP removal has a limited life expectancy, TN removal does not TP is removed by filtration and chemical means. BAM will need to be maintained every 20 years TSS is removed through filtration, which is considered indefinite



## How?



### **BAM Details**

- · Specifications for BAM have not yet been developed
- BAM is the only BMP recognized for use in SKA
  - Other measures do not receive credit (i.e., reduction in fertilization.
     Florida Friendly Landscape, Low Impact Development, BMPs)
- BAM placement and quantity is yet to be finalized
  - Placed over entire pond bottom or only Water Quality Treatment area?
- Sensitive Karst Area (SKA) is being treated as 100% uniform soil profile of 'A' soils (sandy)
  - Some areas have clayey soils with slower infiltration and characteristics, hence additional treatment for Nitrogen removal
  - Site testing studies proposed
  - General application area versus site specific site conditions application

выпитрошири залукуна относогов сооргоского

ANTERNATION COMMISSION OF THE PROPERTY OF THE

# \* ±2.14 acre site 9,100 sf commercial building Retention pond with outfall \* SJRWMD/ Alachua County Sensitive Karst Area (SKA) "Vulnerable"

# Case Study: Dollar General Archer Road



### New Design Criteria per Draft Manual

- 1. Required nutrient removal: 70% for TN, 80% for TP
- 2. Site is located within Hogtown Creek HUC12 watershed (impaired for TP and Fecal Coliform), so required to make a 10% net improvement from pre-development loading (Required TN removal increases to 74%). Even though the site is ±3 miles away from Hogtown Creek and has no way to drain there.
- 3. (Not applicable no direct discharge to OFW)
- 4. SKA "Vulnerable" requires minimum 2 ft. of BAM over the pond bottom and sides.

Shimming all signs and an additional angular and a community of the commun

proposition community

# Case Study: Dollar General Archer Road



# Design Analysis: Surface Water Quality Treatment

Evaluation Criteria	Nitrogen (TN)	Phosphorus (TP)
1 Required Minimum Nutrient Removal	70%	80%
2. Impaired Water Bodies Nutrient Removal	73.8%	74.1%
Nutrient Removal Efficiency Provided by Existing Design	98.9%	98.9%
Performance Criteria Met by Existing Design	YES	YES

- Pollutant removal for surface water discharge is provided by retaining 3.89" over the drainage area
- No design change is required to meet new surface water quality discharge standards

planning.com/pp.:norveying.mg/mp.com/ruction

bindrosamillo) compularità

# Case Study: Dollar General Archer Road



### **Design Analysis: Ground Water Quality Treatment**

- Required performance standard: reduce post-development nitrate loading into the ground water by at least 70%
- 2' of BAM is the only BMP solution allowed

Construction cost for the existing code-compliant pond: \$18,000

Construction cost for new manual compliant pond: \$64,500

Additional cost due to new manual requirements: \$46,500

Estimated Post-Development Nitrogen Loading: 13.31 lbs/year Presumed 70% Nitrogen loading reduction: 9.32 lbs/year

planning design, surveying application of construction

ORDHOGEROUS CONTRACTOR

# Case Study: Dollar General Archer Road





### **Summary and Conclusions**

- Original retention design exceeds the proposed pollutant removal criteria for surface water discharge.
- Reduced infiltration rates of BAM cause increase in pond volume to meet freeboard requirements
  - Make pond bottom 0.5 ft. deeper or
  - Expand the pond laterally by 1 ft.
- Net effect on Developable Area: No change
- Cost of Stormwater Pond: Increased \$46,500 (+361%)
- Net Improvement to Water Quality: 9.32 lbs TN/ year

phonogramma surveyon maintenancementorion

PROFESSIONAL CONTOURNS:





# Case Study: Oakmont Phase 2



### **Increased Stormwater Facility Costs**

### **BAM Material:**

- → BAM Material Used: Bold & Gold
- Cost of Procurement and installation: \$200 / CY
  - Total Cost: \$2,114,058

### Earthwork Costs:

- Excavation and disposal of waste material; \$8 / CY
  - Total Cost: \$210,067

### Impact on Lot Value:

- Total lot sales value = \$11,338,000 (for 186 lots)
- Increased costs = \$2,114,000 + \$210,067 = \$2,324,067 for new stormwater requirements
- Increased cost represents 20% of the original sale value, builder must either.
  - Increase the lot sale value to cover the additional cost lots become less affordable to the buyer
  - Make less money due to increased cost
- · Choose not to build and make no money if the margins decrease to the point that it isn't worthwhile to build
- Average Cost = \$73,452 / lot

опитовка осново воскинное синиванине свеническае

CONTRACTOR OF THE PROPERTY OF

# Case Study: Oakmont Phase 2



### **Summary and Conclusion:**

### Impact on Lot Value:

- Total lot sales value = \$11,338,000 (for 186 lots)
- Increased costs = \$2,114,000 + \$210,067 = \$2,324,067 for new stormwater requirements
- Increased cost represents 20% of the original sale value, builder must either
  - Increase the lot sale value to cover the additional cost lots become less affordable to the buyer
  - Make less money due to Increased cost
  - Choose not to build and make no money if the margins decrease to the point that it isn't worthwhile to build
- Original Cost per lot: \$56,974 / lot
- Under new Alachua County Design Standards: \$73,452 / lot
- Increase in lot cost: ~\$16,500 / lot
- Loss of a minimum of 2.99 AC of developable area
- Future maintenance

plantaling desting serveying engineering construction

THE RESERVE OF THE PERSON NAMED IN COLUMN 1

# Case Study: Oakmont Phase 2



### **Summary and Conclusion:**

What about maintenance?

- Not yet well defined
- Expectation is that BAM will need to be periodically replaced, replacement frequency may be based on limitations of component materials
- Informal data from technical consultant indicates BAM may need to be replaced every 20 years
- For Oakmont, if BAM must be replaced in 20 years, then residents (via the HOA) will have to bear the cost of replacing the BAM in the basins at a cost of \$2.1 million (2016 dollars), increased for inflation
- Other alternatives may be developed before the BAM must be replaced

planning/dusion substrying/orginoen/ig/comit/oshion.

URBHESHIGKUT KONSKITHINE

## Santa Fe River BMAP: BMPs



- Lower Santa Fe River is an impaired water body for Dissolved Oxygen and Nutrients
- Santa Fe River BMAP (Basin Management Action Plan) was adopted in 2012
- TMDL (Total Maximum Daily Load) target 0.35 mg/L for Nitrate (vs. 10 mg/L groundwater drinking water standards)
- Nitrate loads from non-point sources needs to be reduced by 35% to meet target
- BMP (Best Management Practice) based
  - "BMPs are individual or combined management and/or structural practices determined through research, field testing, and expert review to be the most effective and practicable means for improving water quality, taking into account economic and technological considerations."
- BMPs must be cost-effective

Are the BMPs proposed in the draft manual cost-effective?

glanning design, vices ling degins in the construction

MOTES NORME CONSULTABLE

# Nitrogen Removal Cost Comparison



- 1. Lake City Wastewater Treatment Plant Upgrades\*:
  - \$22.5 million / 77,000 lbs TN/yr = \$292 per lb TN/yr
- 2. Agricultural BMPs (FDACS "Fertigation" projects)\*:
  - \$990,000 / 964,000 lbs TN/yr = \$1.03 per ib TN/yr
- 3. BAM (Bold & Gold) for Dollar General Archer Rd
  - \$46,500 / 9.32 lbs TN/yr = \$4,989 per lb TN/yr
- 4. BAM (Bold & Gold) for Oakmont Phase 2
  - \$2.32 million / 363.7 lbs TN/yr = \$6,391 per lb TN/yr

\*Source: 2013 Progress Report for the Santa Fe River BMAP

numming design and a polynomial design and a polynomial a

gratematicant resonance to

### Nitrogen Removal Cost Comparison CHM **Nitrogen Removal Costs** Using BAM in a retention \$7,000 \$6,391 (per lb of Nitrogen/year) pond is a very expensive method for Nitrogen \$6,000 removal \$4,989 \$5,000 BAM is required for all retention ponds in SKA, \$4,000 regardless of site soil conditions \$3,000 Costs for WWTP and Ag \$2,000 BMPs are partially subsidized \$1,000 \$292 \$1 No proposed subsidies for BAM Lake City WWTP Ag BMPs BAM in Dollar BAM in Oakmont Ph. General Archer Rd 2 Retention Pond Retention Pond

# Summary



- We all care about water quality
- The contents of the proposed manual exhibit some inconsistences and areas that require clarification
- The costs associated with the proposed stormwater treatment are they acceptable? (Per Santa Fe River Basin BMAP, BMPs must be cost effective)
- Next steps?

# Task Force Letter (BCC)



Dear Chair Hytchingon.

The Busine's Community Cualition (BCC), a garmership between the Gainesville Area Chamber of Commerce, the Builders Association of North Control Florida, and the Gainesville-Alachus County Alzociation of Regitors, respectfully urges the Alachus County Board of County Coatmissioners (BoCC) to casure that the tromwater policy fermulation process is deliberative, inclusive, and thoughtfully conceived

We recommend that the BoCC establish an Alachus County Stammenter Quality Fahmenings of Task Force to identify and commend policies enhancing surface and ground water quality in Ala-241 Comby. The mix-rou would be in balance environmental protectics and effords tilly through policy recommendations based on science and footily derived data.

We suggest the Task Force would comest of no more than lifteen members with the BoCC, the Aluchus County League of Cities, and the BCC erch appointing five members. It would meet from July - December 2016 and transmit a report with policy recommendations to the BoCC no later then February 1, 2017. The Deputy County Manager would serve as Executive Director of the Task Force and provide staff support in preparing the neceting agendar and the report.

We also respectfully supe the BoCC and to revise my atomicanter regulations until after the Trisk Force has examitted its report with policy recommendations.

Dent R. Che thine, M.B.A. 2015/2016 Cheir, Rusineer Commun.

Alachus Connty Commission catablish a Stormwater Quality Enhancement Task Porce to identify and recommend polities enhancing surface and ground vister quality in Alachua County,

Balance environmental protection and affor liability through policy recommends (our, based on science and locally derived data.

Monthership
The Task Force would consist of  $\epsilon_0$  more than fifteen (15) members who would be selected as follows: Five (5) members appointed by the Alachua County Board of County Commissions and five (5) members appointed by the Alachua County League of Cities, (ive (5) members appointed by the Business Community Coalities.

The Task Force would meet from July 2016 - December 2016 and transmit a regret with policy recommendations to the Alachan County Commission no later it as February 1, 2017.

Executive Director

The Deputy County Manager would serve as Executive Detector of the Task Force and provide CAST support to the Teak Force, aid in preparing and distributing exceeding agencial prior to moeting), and aid in preparing the Task Force report with policy recome

Operation
The Tank Force would elect its own Chair and Vice Chair, "The Chair would get meeting agendas,

The Task Force would meet no loss than or se see month.

The Task Porce may existe aboutamittee



